

**ALBERTA LENTIC WETLAND HEALTH ASSESSMENT (Survey)**  
**USER MANUAL**  
**(Current as of 5/19/2016)**

This document is intended to accompany the *Alberta Lentic Wetland Health Assessment (Survey) Form* for the rapid evaluation of the functional health status of lentic (still water) wetlands. Other forms are available for lotic (flowing water) wetlands.

**ACKNOWLEDGEMENTS**

Development of these assessment tools has been a collaborative and reiterative process. Many people from many agencies and organizations have contributed greatly their time, effort, funding, and moral support for the creation of these documents, as well as to the general idea of devising a way for people to look critically at wetlands and riparian areas in a systematic and consistent way. Some individuals and the agencies/organizations they represent who have been instrumental in enabling this work are Dan Hinckley, Tim Bozorth, and Jim Roscoe of the USDI Bureau of Land Management in Montana; Karen Rice and Karl Gebhardt of the USDI Bureau of Land Management in Idaho; Bill Haglan of the USDI Fish and Wildlife Service in Montana; Barry Adams and Gerry Ehlert of Alberta Sustainable Resource Development; Lorne Fitch of Alberta Environmental Protection; and Greg Hale and Norine Ambrose of the Alberta Cows and Fish Program.

**BACKGROUND INFORMATION**

**Introduction**

Public and private land managers are being asked to improve or maintain wetland (lentic) habitat and water quality on lands throughout the western North America. Three questions that are generally asked about a wetland site are: 1) What is the potential of the site (e.g., climax or potential natural community)? 2) What plant communities currently occupy the site? and 3) What is the overall health (condition) of the site? For a lentic (still water) site, the first two questions can be answered by using the Alberta Lentic Wetland Inventory Form along with a document such as *Classification and Management of Riparian and Wetland Sites of the Alberta Grassland Natural Region and Adjacent Subregions* (Thompson and Hansen 2002), *Classification and Management of Riparian and Wetland Sites of Alberta's Parkland Natural Region and Dry Mixedwood Natural Subregion* (Thompson and Hansen 2003), *Classification and Management of Riparian and Wetland Sites of the Saskatchewan Prairie Ecozone and Parts of Adjacent Subregions* (Thompson and Hansen 2001) or a similar publication written for the region in which you are working.

This *Lentic Wetland Health Assessment (Survey)* is a method for rapidly addressing the third question above: What is the site's overall health (condition)? It provides a site rating useful for setting management priorities and stratifying wetland sites for remedial action or closer analytical attention. It is intended to serve as a first approximation, or coarse filter, by which to identify lentic wetlands in need of closer attention so that a manager can more efficiently concentrate effort. We use the term lentic (still water wetland) health to mean the ability of a lentic wetland to perform certain functions. These functions include sediment trapping, shoreline maintenance, water storage, aquifer recharge, wave energy dissipation, maintenance of biotic diversity, and primary production.

**Flowing Water (Lotic) vs. Still Water (Lentic) Wetlands**

Cowardin and others (1979) point out that no single, correct definition for wetlands exists, primarily due to the nearly unlimited variation in hydrology, soil, and vegetative types. Wetlands are lands transitional between aquatic (water) and terrestrial (upland) ecosystems. Windell and others (1986) state that wetlands are part of a continuous landscape that grades from wet to dry. In many cases, it is not easy to determine precisely where they begin and where they end.

In the semiarid and arid portions of western North America, a useful distinction has been made between wetland types based on association with different aquatic ecosystems. Several authors have used *lotic* and *lentic* to separate wetlands associated with running water from those associated with still water. The following definitions represent a synthesis and refinement of terminology from Shaw and Fredine (1956), Stewart and Kantrud (1972), Boldt and others (1978), Cowardin and others (1979), American Fisheries Society (1980), Johnson and Carothers (1980), Cooperrider and others (1986), Windell and others (1986), Environmental Laboratory (1987), Kovalchik (1987), Federal Interagency Committee for Wetland Delineation (1989), Mitsch and Gosselink (1993), and Kent (1994).

**Lentic wetlands** are associated with still water systems. These wetlands occur in basins and lack a defined channel and floodplain. Included are permanent (i.e., perennial) or intermittent bodies of water such as lakes, reservoirs, potholes, marshes, ponds, and stockponds. Other examples include fens, bogs, wet meadows, and seeps not associated with a defined channel.

**Lotic wetlands** are associated with rivers, streams, and drainage ways. They contain a defined channel and floodplain. The channel is an open conduit, which periodically or continuously carries flowing water. Beaver ponds, seeps, springs, and wet meadows on the floodplain of, or associated with, a river or stream are part of the lotic wetland.

### **Functional vs. Jurisdictional Wetland Criteria**

Defining wetlands has become more difficult as greater economic stakes have increased the potential for conflict between politics and science. A universally accepted wetland definition satisfactory to all users has not yet been developed because the definition depends on the objectives and the field of interest. However, scientists generally agree that wetlands are characterized by one or more of the following features: 1) **wetland hydrology**, the driving force creating all wetlands, 2) **hydric soils**, an indicator of the absence of oxygen, and 3) **hydrophytic vegetation**, an indicator of wetland site conditions. The problem is how to define and obtain consensus on thresholds for these three criteria and various combinations of them.

Wetlands are not easily identified and delineated for jurisdictional purposes. Functional definitions have generally been difficult to apply to the regulation of wetland dredging or filling. Although the intent of legislation is to protect wetland functions, the current delineation of jurisdictional wetland still relies upon structural features or attributes.

The prevailing view among many wetland scientists is that functional wetlands need to meet only one of the three criteria as outlined by Cowardin and others (1979) (e.g., hydric soils, hydrophytic plants, and wetland hydrology). On the other hand, jurisdictional wetlands need to meet all three criteria, except in limited situations. Even though functional wetlands may not meet jurisdictional wetland requirements, they certainly perform wetland functions resulting from the greater amount of water that accumulates on or near the soil surface relative to the adjacent uplands. Examples include some woody draws occupied by the *Acer negundo/Prunus virginiana* (Manitoba maple/choke cherry) habitat type (Thompson and Hansen 2002) and some floodplain sites occupied by the *Artemisia cana/Agropyron smithii* (silver sagebrush/western wheat grass) habitat type or the *Populus tremuloides/Cornus stolonifera* (aspen/red-osier dogwood) habitat type. Currently, many of these sites fail to meet jurisdictional wetland criteria. Nevertheless, these functional wetlands provide important wetland functions vital to wetland dependent species and may warrant special managerial consideration. The current interpretation is that not all functional wetlands are jurisdictional wetlands, but that all jurisdictional wetlands are functional wetlands.

### **Lentic Wetland Health**

The health of a lentic site (a wetland located adjacent to a still water body) may be defined as the ability of that system (including the saturated and inundated near-shore emergent wetland and all the shoreline area that is influenced by the lentic waters) to perform certain wetland functions. These functions include sediment trapping, shoreline maintenance, water storage, aquifer recharge, wave energy dissipation, primary biotic production, and wildlife habitat. A site's health rating may also reflect management considerations. For example, although *Centaurea maculosa* (spotted knapweed) or *Euphorbia esula* (leafy spurge) may help to trap sediment and provide soil-binding properties, other functions (i.e., productivity and wildlife habitat) will be impaired; and their presence should be a management concern. Excellent sources of practical ideas and tips on good management of these wetland sites in Alberta are found in *Caring for Shoreline Properties* (Valastin and others 1999) and *Caring for the Green Zone* (Adams and Fitch 1995), and *Riparian Areas: A User's Guide to Health* (Fitch and Ambrose 2003). In Saskatchewan some excellent resources are *Streambank Stewardship, Your Guide to Caring For Riparian Areas in Saskatchewan* (Huel 1998) and *Managing Saskatchewan Wetlands—A Landowner's Guide* (Huel 2000).

No single factor or characteristic of a wetland site can provide a complete picture of either site health or the direction of trend. The lentic wetland health assessment is based on consideration of physical, hydrologic and vegetation factors. It relies heavily on vegetative characteristics as integrators of factors operating on the landscape. Because they are more visible than soil or hydrological characteristics, plants may provide early indications of riparian health as well as successional trend. These are reflected not only in the types of plants present, but also by the effectiveness with which the vegetation carries out its wetland functions of stabilizing the soil, trapping sediments, and providing wildlife habitat. Furthermore, the utilization of certain types of vegetation by animals may indicate the current condition of the wetland and may indicate trend toward or away from potential natural community (PNC).

In addition to vegetation factors, an analysis of site health and its susceptibility to degradation must also consider physical factors (soils and hydrology) for both ecologic and management reasons. Changes in soil or hydrologic conditions obviously affect the function of a wetland ecosystem. Moreover, degradation in physical characteristics are often (but not always) more difficult to remedy than vegetative degradation. For example, downcutting of an unstable overflow point may lower the water table and thus change site potential from a *Typha latifolia* (common cattail) habitat type to an *Agropyron smithii* (western wheat grass) habitat type or even to an upland type. Sites experiencing significant hydrologic, edaphic (soil), or climatic changes will likely also have new plant community potential.

This health assessment is not designed to serve as an in-depth and comprehensive analysis of ecologic processes. Such analysis may be warranted on a site and can be done after this evaluation has identified particular areas of concern. Nor does this approach yield an absolute rating to be used in comparison with wetlands in other areas or of other types. Appropriate comparisons using this rating can be made between neighbouring wetlands of similar size and type and between subsequent assessments of the same site.

The assessment procedure has been tested in Montana, Idaho, North Dakota, South Dakota, and other surrounding states and western Canada since 1992. Some potential uses for this rating are: 1) for stratifying wetlands by degree of ecologic dysfunction, 2) for identifying ecologic problems, and 3) when repeated over time, for monitoring to detect functional change. A less direct, but also important, value of an environmental assessment of this kind is its educational potential. By getting land managers to focus on individual riparian functions and ecologic processes, they may come to better understand how the parts work together and are affected by human activities.

A single evaluation provides a rating at only one point in time. Due to the range of variation possible on a wetland site, a single evaluation cannot reliably indicate trend (whether the site is improving, degrading, or stable). To monitor trend, health assessments should be repeated in subsequent years during the same time of year. Evaluation should be conducted when most plants can be identified in the field and when hydrologic conditions are most nearly normal (e.g., not during peak spring runoff or immediately after a major storm). Management regime should influence assessment timing. For example, in assessing trend on rotational grazing systems, one should avoid comparing a rating after a season of use one year to a rating another year after a season of rest.

There are some visible changes to riparian area health which we have no simple way to measure. An obvious and commonly encountered example is excess entrained sediment. This may indicate serious degradation, but we leave it out of the assessment due to difficulty in knowing how much is normal. Instead, we address on-site causes of sediment production: bare ground, shoreline with poor root mass protection, and human-caused structural damage to the shoreline.

### **Pre-Assessment Preparation**


The lentic health assessment process incorporates data on a wide range of biological and physical categories. The basic unit of delineation upon which an assessment is made is referred to as a **polygon**. A lentic polygon is a wetland, or portion of a wetland, not associated with a waterway (stream or river) and which has no defined channel. Polygons are delineated on topographic maps before evaluators go to the field. It is important to clearly mark and number the polygons on the maps.

If aerial photos are available, polygon delineations can be based on vegetation differences, geologic features, or other observable characteristics. On larger systems with wide wetland areas, aerial photos may allow delineation of multiple vegetation-based polygons away from the water source. In these cases, where polygons can be drawn as enclosed units a minimum mapping unit of possibly 2 to 4 ha (5 to 10 ac) should be followed. The size of the minimum mapping unit should be based on factors such as management capabilities, available funds, and capabilities of data collection.

If pre-delineated polygons are drawn on the maps, and pre-assigned numbers are given, be sure the inventoried polygons correspond exactly to those drawn. Evaluators are allowed to move polygon boundaries, create new polygons, or consolidate polygons if the vegetation, geography, location of fences, or width of the wetland zone warrant. If polygon boundaries are changed, the changes must be clearly marked on the field copies of the maps. Evaluators should draw the complete polygon boundary onto their field maps if possible at the 1:20,000 or 1:50,000 scale.

In most cases involving small bodies of water or small lentic wetlands, the inventoried polygon will be a single unit of area. Around larger lakes, extensive marshes, or other large lentic wetlands, it may be necessary to divide the wetland into separate polygons (Figure 1). Polygons should be divided at distinct locations such as fences, stream entrances or exits, or other features easily recognized in the field. When selecting representative sites, consideration should be given to the differences

presented by landform position (i.e., point vs. bay, or windward vs. leeward side of the water body). **Polygons should not cross fences between areas with different management.**



**Figure 1.** Schematic drawing of a lentic (still water) wetland showing: 1) delineation of polygons on larger systems, i.e. those too big to inventory as a single polygon (more than about 0.5 mi [1.6 km] in length) or those with managerial breaks crossing them; 2) a typical relationship between deep water habitat (lacking emergent vegetation) and surrounding lentic wetland, which includes all areas of persistent emergent vegetation in standing water.

The outer boundaries of polygons are usually at the wetland ecosystem outer edges. These boundaries are sometimes easily determined by abrupt changes in the landform and/or vegetation, but proper determination often depends on experienced interpretation of more subtle features. Do not include deep water habitat within the polygon area. The inner polygon boundary is the landward edge of the deep-water habitat, or where persistent emergent vegetation gives way to open water. In concept, deep-water habitat is the area covered by surface water deeper than 2 m (6.6 ft), or where sunlight cannot penetrate to support persistent, erect, rooted, plant life. Persistent emergent vegetation consists of species that normally remain standing at least until the beginning of the next growing season, e.g., *Typha* species (cattails) or *Scirpus* species (bulrushes). In practice, include all emergent vegetation (i.e., go out to open water) regardless of depth. If emergent vegetation has been removed by human activity, include out to where it would be expected in the absence of that impact. If there is no emergent vegetation, and there is no apparent potential for it, then stop the polygon where persistent vegetation ends and the open water begins.

In cases where observer access and visibility on part of the site to be assessed is impeded by deep water that may have extensive areas of emergent vegetation, the observer may choose, with documented reason, to either:

- Break the area into separate polygons in cases where large areas are utilized differently, such as where the landward area (onshore) is heavily impacted by human use and the wetted area (marsh) is unimpacted;
- Draw an arbitrary outer edge of the polygon that does not include all of the area with emergent vegetation, in which case the observer must carefully document the delineation and the rationale employed; or
- Include the entire dry and wet area together in a single polygon with careful commentary noting any areas that may be impacted differently due to having such greatly different conditions.

When using the lentic survey on artificial or artificially enlarged waterbodies (e.g. dugout, manmade pond, reservoirs), use the same criteria, but remember that some questions may be difficult to apply appropriately. Focus on being consistently applying the methods, including delineation of site boundaries. Remember to record all decisions made in applying the methodology. The goal is to assess the site's ability to perform ecological functions *to its potential*.

Identification of plant communities by vegetation type (such as Thompson and Hansen 2002, Thompson and Hansen 2003, Thompson and Hansen 2001, or other classification appropriate to the region where you are working) will be useful both in site selection and, later, in determining appropriate management. These communities may be in a mosaic difficult to map. An area may have a mix of herbaceous communities, shrubs, and forest. These communities have diverse resource values and may respond differently to a management action, but it is seldom practical to manage such communities separately. Community composition can be described as percentages of component types. Management actions can then be keyed to the higher priority types present.

## DATA FORM ITEMS

**Record ID No.** This is the unique identifier allocated to each polygon. This number will be assigned in the office when the form is entered into a database.

**Polygon No.** Polygon number is a sequential identifier of the actual piece of land being surveyed. This is referenced to the water body code list from the Training Manual.

### Administrative Data

**A1.** Identify what organization is doing the evaluation field work.

**A2.** Identify what organization is paying for the work.

**A3.** Date that the field data was collected: Use the format: month/day/year.

**A4.** Record the year that the field data was collected.

**A5.** Observers: Name the evaluators recording the data in the field.

*Land ownership may include more than one entity or person, but more than one type of landownership (eg. private and government) should only be selected after considering a number of factors. Factors to consider are the level of detail that the client is looking to extrapolate, the proportion of the area relative to the rest of the polygon and whether it is a typical situation where the multiple types (e.g., crown or non crown land) will not be included. For example, where very minimal Crown bed and shore area exists within the polygon (such as just at the waterline), as part of a primarily privately owned parcel, the private ownership may be listed as the only ownership type.*

**A6a.** Indicate whether the polygon is representative, which requires that stratification has been done to assist in selection of representative sites. Answer "Yes," "No," or "Unknown."

**A6b.** If A6a was answered "Yes," select the broadest (largest) scale at which the site is representative. For example, if it is representative (based on stratification) of both the "project area" and the "land holding," then choose "project area," to indicate the site represents the larger area. The choices are:

- Representative of a water body (may include multiple management units or land holdings);
- Representative of a management unit within a land holding;
- Representative of a land holding that may contain multiple management units;
- Representative of a project area that may contain multiple land holdings; or
- Unknown

**A6c.** Identify how the site was selected or chosen by choosing one of the options. (**ANSWER THIS QUESTION REGARDLESS OF THE ANSWER TO QUESTION A6a.**)

- Random (i.e., some objective random method was used to pick the site location.);

- Selective (i.e., the site location was chosen for some reason; such as sign up lists, demonstration site, project monitoring, or other particular criteria.); (**Note:** Representative sampling [A6b] can include sites chosen randomly or selectively); or
- Unknown

**A7a, b.** Identify any National, Provincial, or Rural/Urban Municipal, or other Park(s) on which work is being done. If Yes, identify which type of park is established. More than one type may occur.

**A7c.** Indicate the full **official** name of the National, Provincial, or Rural/Urban park on which work is being done. If Other kind of park, identify the type of park and its established name.

**A8a, b.** Identify any **other types of protected areas** on which work is being done. If Yes, properly identify the type and name of the protected area that is established. (**Exclude National, Provincial, or Rural/Urban, or other Park(s) recorded in A7.**)

This question includes all areas with regulatory or administrative protection, other than parks, which are covered in A7. There are many types, including:

**Conservation Easement** are land with a registered easement for the purposes of maintaining conservation value.

**Ecological Reserves** are areas of Crown Land (Provincial Government), which have the potential to contain representative, rare and fragile landscapes, plants, animals and geological features. The intent is for the preservation of natural ecosystems, habitats and features associated with biodiversity. Public access to ecological reserves is by foot only; public roads and other facilities do not normally exist and will not be developed.

**Environmental Reserve** generally are those lands that are considered un-developable and may consist of a swamp, gully, ravine, coulee or natural drainage course, flood prone areas, steep slopes or land immediately adjacent to lakes, rivers, stream or other bodies of water. Governed by *The Municipal Government Act (Alberta)*.

**Municipal Reserve** may also be known, in part, as reserve, park reserve, park or community reserve. Municipal reserves are lands that have been given to the municipality by the developer of a subdivision as part of the subdivision approval process. Governed by *The Municipal Government Act (Alberta)*.

**Other Types of Protected Area (Designated Nationally, Provincially, or Municipally)** such as, Provincial Recreation Areas, Wilderness areas, Natural Areas, Heritage Rangelands, National Historic Sites, and Migratory Bird Sanctuaries.

**A9.** If this polygon has an association with a Watershed Group/Community Affiliation name the group.

**A10.** Identify the organizations project name. This may be a internal name not recognized by the Watershed Group or Community Affiliation but a name used to group a series of polygons. Use “Individual” if not a group and not a demo.

**A11.** Identify if work was done on Private Land? Answer Yes or No. If applicable give the Landowners Name.

**A12a-d.** Identify if work is being done on Private Land that is rented out? Answer Yes or No. If applicable give Renters Name, their Legal Land Description of residence, and County name, if different from the one where the work is being done.

**A13a-c.** Public Land is land that is administered by a Federal, Provincial, or Municipal agency. Provincial Public lands are owned by the provincial government and administered under the authority of the Public Lands Act. Identify if work was done on Public Land. Answer “Yes” or “No.” If applicable give Managers Name, as well as the Provincial office and their department associated with the management of this land to which work is being done.

**A14a.** Identify if site is a Grazing lease or Grazing reserve on which work is being done. If applicable give Lessees/Group name.

**A14c.** Identify which Disposition this land falls under and its license number associated with it. i.e., GRL: Grazing Lease, GRP Grazing Permit, GRR Grazing Reserve, FGL Forest Grazing License, CUP Cultivation Permit.

**A14d.** Give any other grazing name (e.g. Community Pasture) to identify where the work is being done.

**A15.** The several parts of these items identify various ways in which a data record may represent a resampling of a polygon that may have been inventoried again at some other time. The data in this record may have been collected on an area that coincides precisely with an area inventoried at another time and recorded as another record in the database. It may also

represent the resampling of only a part of an area previously sampled. This would include the case where this polygon overlaps, but does not precisely and entirely coincide with one inventoried at another time. One other case is where more than one polygon inventoried one year coincides with a single polygon inventoried another year. All of these cases are represented in the database, and all have some value for monitoring purposes, in that they give some information on how the status on a site changes over time. ***This is done in the office with access to the database; field evaluators need not complete these items.***

**A15a.** Has any part of the area within this polygon been inventoried previously, or subsequently, as represented by another data record in the database? Such other records would logically carry different dates as well as Identification Numbers.

**A15b.** If A15a is answered Yes, then enter the years of any inventories of this exact polygon.

**A15c.** Does the area extent of this polygon exactly coincide with that of any other inventory represented in the database? In many cases, subsequent inventories only partially overlap spatially.

**A15d.** If A15c is answered Yes, identify those database record ID numbers for other polygons that can be compared as representing exactly the same ground area.

**A16a.** Even though this polygon is not a re-inventory of the exact same area as any other polygon, does it share at least some common area with one or more polygons inventoried at another time?

**A16b.** If A16a is answered Yes, enter the record ID number(s) of any other polygon(s) sharing common area with this one.

**A17a, b.** Has a management change been implemented on this polygon or that directly/clearly influences the polygon? Simply answer “Yes,” “No,” or “Unknown.” If applicable, in what year was the management change implemented and describe the management change implemented?

**A18.** *The primary contact is the person (landowner, land manager, or renter, etc.; include agency name if appropriate) who initiated the contact with the funding organization to have this riparian work conducted. Therefore, if the renter initiated the contact, the land owner would be a secondary contact.*

#### **Location Data**

**B1.** Province in which the field work is being done (i.e., where the polygon is located).

**B2.** Municipality or Reserve Type: (drop down list in the database). Choose one of the following: **Indian Reserve, Military Reserve, Rural Municipality** (*MD or County, Hamlet, Improvement District [which includes all National Parks]*), *Métis Settlements, Special Areas, Specialized Municipality (5 in the province)* or **Urban Municipality** (*City, Town, Village, Summer Village*). ***For further clarification on the three types of Municipalities in Alberta, see insert in the back of the field manual.***

**B3a.** Indian Reserve Name (drop down list in database)

**B3b.** Military Reserve Name (drop down list in database)


**B4a, b.** Rural or Specialized Municipality Name (drop down list in database). If applicable, list the Hamlet name in B4b.

**B5a-d.** The name of the city, town, or village in which the fieldwork is being done. If applicable list the subdivision plan number, block number and lot number of the area to which the work was being done on.

**B6a.** Name the water body or area on which the field work is being done.

**B6b.** Identify the side of the polygon that the Assessment is completed for by using North, South, East or West, if assessment includes both sides enter Both.

**B7.** The location of the polygon is presented as a legal land description (1/4, 1/4 section, 1/4 section, Township, Range, and Meridian) are read from smallest to largest unit.



**B8a, b.** Identify the Natural Region and Sub-Region in which the field work is being done. Use the Natural Regions and Subregions of Alberta (Alberta Natural Heritage Information Centre [1999]).

**B9a.** Name the major watershed (e.g. North Saskatchewan River) of which the site being surveyed is a part. List one of the seven major Basins by AESRD: Hay River, Peace/Slave River, Churchill River, North Saskatchewan River, South Saskatchewan River, and Missouri River Watersheds.

**B9b.** Name the minor watershed (e.g. Battle River) of which the site being surveyed is a part. This is normally subordinate to the major watershed named above in B10a.

**B9c.** Name the sub-basin in which you are working (e.g. Iron Creek). This is the third level down from the largest (major watershed) (e.g., North Saskatchewan River—Battle River—*Iron Creek*; or South Saskatchewan River—Red Deer River—*Little Red Deer River*). Although you may be working on an even lower level tributary, the sub-basin flows directly into and is subordinate to the minor watershed named above in B9b. If you are doing a site on a Major or Minor Watershed, then the Sub-basin may be the same as the Major or Minor basin, respectively.

**Additional Example:** You are doing an inventory on Pekisko Creek—*this creek is not the sub-basin*. The order should be: South Saskatchewan River—Bow River—Highwood River.

**B10a-c.** Universal Transverse Mercator (UTM) coordinates s are recorded for the northern/western and southern/eastern ends of the polygon using GPS units in the field. Other locations of special interest may be recorded using the GPS unit. These coordinates s are considered accurate to within approximately 10 m (33 ft). Field observers are to use GPS units to obtain these coordinates s following standard protocol. Record UTM coordinates s at each end of the long axis of the polygon.

Enter the UTM coordinates data, including the UTM zone and the identifying waypoint number, on the form for each point collected. Save the data in the GPS unit for downloading to the computer later. When starting work in a new location, always check the GPS receiving unit against a known point by using the UTM grid and map.

**B10d, e.** Identify the GPS unit used, and the name or number designator of the waypoints saved for the northern/western and southern/eastern ends of the polygon and for other locations. Describe any comments worth noting about the waypoints (i.e., monument referenced or general location descriptions).

**B11a-c.** Record the name(s), scale, and publication year of the quadrangle map(s) or any other map(s) locating the polygon. Use precisely the name listed on the map sheet. Provision is made for listing two maps in case the polygon crosses between two maps.

**B12.** Record identifying data for any aerial photos used on this polygon.

### Selected Summary Data

**C1.** Wetland type is a categorical description of predominant polygon character. Select from the following list of categories that may occur within a lentic system the one that best characterizes the majority of the polygon. Evaluators will *select only one category* as representative of the entire polygon. If significant amounts of other categories are present, indicate this in the General Comments, or consider dividing the original polygon into two or more polygons.



---

## Category Description

---

**Wet Meadow.** A grassland with waterlogged soil near the surface, but without standing water for most of the year. This type of wetland may occur in either riparian (lotic) or in still water (lentic) systems. A lotic wet meadow has a defined channel or flowing surface water nearby, but is typically much wider than the riparian zone associated with the classes described above. This is often the result of the influence of lateral groundwater not associated with the stream flow. Lotic and lentic wet meadows may occur in proximity (e.g., when enough groundwater emerges to begin to flow from a mountain meadow, the system goes from lentic to lotic). Such communities are typically dominated by herbaceous hydrophytic vegetation that requires saturated soils near the surface, but tolerates no standing water for most of the year. This type of wetland typically occurs as the filled-in basin of old beaver ponds, lakes, and potholes.

**Marsh.** A frequently or continually inundated wetland characterized by emergent herbaceous vegetation adapted to saturated soil conditions. A marsh generally has a mineral soil substrate does not accumulate peat.

**Fen.** A peat-accumulating wetland that receives some drainage from surrounding mineral soil and usually supports marsh-like vegetation.

**Bog.** A peat-accumulating wetland that has no significant inflows or outflows and supports acidophilic mosses, particularly sphagnum.

**Spring/Seep.** Groundwater discharge areas. In general, springs have more flow than seeps. This wetland type may occur in a riparian (lotic) or still water (lentic) system.

**Reservoir.** An artificial (dammed) water body with at least 8 ha (20 ac) covered by surface water.

**Stock Pond.** An artificial (dammed) body of water of less than 8 ha (20 ac) covered by surface water.

**Lake.** A natural topographic depression collecting a body of water covering at least 8 ha (20 ac) with surface water.

**Pothole, Slough, or Small Mountain Lake.** A natural topographic depression collecting a body of water covering less than 8 ha (20 ac) with surface water.

**Other.** Describe any other wetland type encountered, which is not associated with a surface water channel.

**Non-wetland (Upland).** This designation is for those areas which are included in the inventoried polygon, but which do not support functional wetland vegetation communities. Such areas may be undisturbed inclusions of naturally occurring high ground or such disturbed high ground as roadways and other elevated sites of human activity.

---

**C2.** The size (acres/hectares) of polygons large enough to be drawn as enclosed units on topographic maps is determined in the office using a planimeter, dot grid, or GIS. For polygons too small to be accurately drawn as enclosed units on the maps, polygon size is calculated using polygon length (item C7) and average polygon width (item C8a).

**C3a-d.** Evaluators may be asked to survey some areas that have not been determined to be wetlands for the purpose of making such a determination. Other polygons include areas supporting non-wetland vegetation types. A Yes answer to C3a indicates that no part of the polygon keys to a riparian habitat type or community type (HT/CT). **Areas classified in item C8 as any vegetation type described in a riparian and/or wetland classification document for the region in which you are working are counted as functional wetlands.** Areas listed as UNCLASSIFIED WETLAND TYPE are also counted as functional wetlands. Other areas are counted as non-wetlands, or uplands. The functional wetland fraction of the polygon area is listed in item C3c in acres and as a percentage of the entire polygon area in item C3d.

**C4.** Lentic wetlands associated with open water, like lakes and ponds, typically have a shore. The **shore** is defined as a variable width area that contains all points reached over time by the water's edge along the water body between its high stage and current water level—i.e., the area that is visibly affected by periods of inundation and drying between seasonal and longer cyclic high and low water levels. (The time frame is generally taken to mean the recent period of hydrologic record, or the extent indicated by physical evidence present.) The **shoreline** is defined much more narrowly as a 1-2 m (3.3-6.6 ft) band stretching along the landward side of the water's edge TODAY. A defined shoreline means there is narrow band or line that is distinctive and distinguishable. Therefore, the actual position of the shoreline shifts over time with water level.

Some lentic polygons may not contain a shore between wetland and open water. In some cases these polygons are in ephemeral depressions which may be infrequently inundated, but do support wetland plant communities. In other cases, these polygons may be part of large marsh systems that may or may not be associated with lakes, but where polygons may be delineated in areas not adjacent to open water.

**C5.** **For all lentic sites indicate length and width directions on sketch page. Polygon length is measured in the office using GIS.** Polygon length may be the same as shoreline length, but may not be in cases of much curved shoreline, or for polygons

that have no shoreline (i.e., wet meadows or marshes). The shoreline is defined as a linear feature extending at the time of observation along the water's edge 1 m (3 ft) wide back from the water onto the land. **For lentic polygons that include the entire site (i.e. there is no inner boundary and no area excluded such as open water [e.g. wet meadow]).** Polygon length will be determined in the office using GIS and will represent the longest axis of the wetland site examined.

**C6.** In some cases, the polygon data is used to characterize, or represent, a much larger, or longer, area. The length represented by the polygon is given. For example, a 0.8 km (0.5 mi) polygon may be used to represent 3.2 km (2 mi) of total shoreline length. In this case, 0.8 km (0.5 mi) is the shoreline length in the polygon (item C5), and 3.2 km (2 mi) is the overall shoreline length entered in item C6.

**C7a.** Record average width of the polygon, which in smaller wetlands corresponds to the width of the entire wetland area. The width (average, minimum and maximum) will be determined in the field as the distance perpendicular to the longest axis.

**C7b.** Record the range of width (ft/m), narrowest to widest, of the wetland area in the polygon.

**C8.** List the riparian habitat type(s) and/or community type(s) found in the polygon using a manual for identifying types in the region in which you are working, such as *Classification and Management of Riparian and Wetland Sites of the Alberta Grassland Natural Region and Adjacent Subregions* (Thompson and Hansen 2002), *Classification and Management of Riparian and Wetland Sites of Alberta's Parkland Natural Region and Dry Mixedwood Natural Subregion* (Thompson and Hansen 2003), *Classification and Management of Riparian and Wetland Sites of the Saskatchewan Prairie Ecozone and Parts of Adjacent Subregions* (Thompson and Hansen 2001) or the applicable Sustainable Resource Development (SRD) Guide for the natural sub-region in which you are working. If the habitat type cannot be determined for a portion of the polygon, then list the appropriate community type(s) of that portion. If neither the habitat type nor community type can be determined for any portion of the polygon (or in areas where the habitat and community types have not been named and described), list the area in question as unclassified wetland type and give the dominant species present. Indicate with the appropriate abbreviation if these are habitat types (HT), community types (CT), or dominance types (DT), for example, SALILUT/CORNSTO HT (*Salix lutea/Cornus stolonifera* [yellow willow/red-osier dogwood] Habitat Type). For each type listed, estimate the percent of the polygon represented. If known, record the successional stage (i.e., early seral, mid-seral, late seral, and climax), or give other comments about the type. As a minimum, list all types that cover 5% or more of the polygon. The total must approximate 100%. Slight deviations due to use of class codes or to omission of types covering less than 5% of the polygon are allowed. **NOTE:** For any area designated as an unclassified wetland type, it is important to list any species present that can indicate the wetness or dryness of the site.

The things listed in item D15 (HTs, CTs, and other coverages) should account for the entire polygon area. These values are used in analyses calculations that must account for the whole polygon. The list of non riparian vegetation types is shown below, but it is somewhat dynamic, so that if others are encountered, they can be added. These other "types" are important to understand what is happening on the polygon.

- Building Complex;
- Gravel Surface (human constructed);
- Paved Surface;
- Cropland;
- Hayfield;
- Open Water;
- Unvegetated Mine Tailings;
- Nonriparian (Upland Type), and;
- Unclassified Wetland Type UNC (as per CF updated protocol [2012] included with Habitat Classification Keys in CF manual).

**NOTE:** Open water in the polygon that does not have emergent vegetation, but that is less than 2 m (6.6 ft) deep is counted as a type called Open Water. The term "Unclassified Wetland Type" signifies a natural vegetation that does not yield a name when put through an HT/CT key, but which can be described by species dominance in upper and lower stories. You normally should only need to use "Unclassified Wetland Type" when working in an area lacking a classification.

### Additional Physical Site Characteristics

**D1a, b.** Make a call on whether the polygon has potential for tall woody type(s), and if the answer is Yes, then tell whether such types are present on the polygon. Tall woody types are any tree habitat types or community types and such taller shrubs as willows, Saskatoon serviceberry, alder, birch, etc. Not included are shorter shrub species, such as buckbrush/snowberry, rose, etc.

**D2a.** (Skip this item if the polygon lacks trees and shrubs **AND** there are no stumps or cut woody plants to indicate that it ever had any and no other evidence [e.g. surrounding landscape or historical imagery] to support your call.) When **NO** remnants remain, use other evidences such as aerial photos or adjacent lands across the fence and explain comments in D2b. An example is “Use air photo X or land across the fence with trees to the north.” Excessive cutting or removing parts of plants or whole plants by agents other than browsing animals (e.g., human clearing, cutting, beaver activity, etc.) can result in many of the same negative effects to the community that are caused by excessive browsing. However, other effects from this kind of removal are direct and immediate, including reduction of physical community structure and wildlife habitat values. **Do not include natural phenomena such as natural fire, insect infestation, etc. in this evaluation.**

- NC - used in database for old polygons when data was not collected and used when insufficient data is available to make a call. Example: no historic photos or nearby comparison areas available.
- NA - site does not have the ability to support trees and shrubs (example: prairie/saline conditions).

Removal of woody vegetation may occur at once (a logging operation), or it may be cumulative over time (annual firewood cutting or beaver activity). This question is not so much to assess long term incremental harvest, as it is to assess the extent that the stand is lacking vegetation that would otherwise be there today. Give credit for re-growth. Consider how much the removal of a tree many years ago may have now been mitigated with young replacements.

Three nonnative species or genera are excluded from consideration because these are aggressive, invasive exotic plants that should be removed. They are *Elaeagnus angustifolia* (Russian olive), *Rhamnus cathartica* (European/common buckthorn), and *Tamarix* species (salt cedar).

Determine the extent to which woody vegetation (trees and shrubs) is lacking due to being physically removed (i.e., cut, mowed, trimmed, logged, cut by beaver, or otherwise removed from their growing position). The timeframe is less important than the ecological effect. Time to recover from this kind of damage can vary widely with site characteristics. The objective is to measure the extent of any damage remaining **today** to the vegetation structure resulting from woody removal. We expect that the woody community will recover over time (re-grow), just as an eroding bank will heal with re-growing plant roots. This question simply asks how much woody material is still missing from what should be on the site? The amount of time since removal doesn't really matter, if re-growth has been allowed to progress. If 20 years after logging, the site has a stand of sapling spruce trees, then it should get partial re-growth credit, but not full credit, since the trees still lack much of their potential habitat and ecological value. (**NOTE:** In general, the more recent the removal, the more entirely it should be fully counted; and conversely, the older the removal, the more likely it will have been mitigated by re-growth.)

This question is really looking at volume (three dimensions) and not canopy cover (two dimensions). For example, if an old growth spruce tree is removed, a number of new seedlings/saplings may become established and could soon achieve the same canopy cover as the old tree had. However, the value of the old tree to wildlife and overall habitat values is far greater than that of the seedling/saplings. It will take a very long time before the seedlings/saplings can grow to replace all the lost habitat values that were provided by the tall old tree. On the other hand, shrubs, such as willows, grow faster and may replace the volume of removed plants in a much shorter time. Answer this question by estimating the percent of woody material that is missing from the site due to having been removed by human action. Select a range category from the choices given that best represents the percent of missing woody material.

**D2b.** Record comments giving evidence for the above call.

**D3.** Give the water body number (FMIS/Hydro code).

**D4a, b.** If water quality data is available on this water body, list the reference where the data can be found.

**D5.** Describe the boundaries of the polygon, especially the location of the upper and lower ends, as well as the lateral boundaries. On smaller streams the polygon usually includes the entire width of the riparian zone. Describe what you use as

the indicators of the wetland-upland boundary. Use localized geologic, physical, or vegetation information to identify these boundaries of the polygon for future polygon relocation.

### **Photograph Data**

**NOTE:** Take benchmark photos at the **INNER** (water's edge) and **OUTER** (inland) boundaries of the polygon. At each benchmark location take photos **OUTSIDE** of the polygon and **INTO** the polygon. For each benchmark location record the waypoint name [POLYGON# with direction, for example LBL2N (water's edge) and LBL2NO (outer boundary)] enter the UTM location coordinates and identify each photo with its photo number and description. Identify and record all photo point locations sufficiently so that they can be relocated by another individual.

**E1a.** At the **northern/western** most end of the polygon take photos at the **inner boundary (water's edge)** looking **OUT** of and **INTO** the polygon. Identify the photo numbers and then enter a description of each photograph taken at the northern/western most end of the polygon.

**E1b.** At the **northern/western** most end of the polygon take photos at the **outer boundary (inland)** looking **OUT** of and **INTO** the polygon. Identify the photo numbers and then enter a description of each photograph taken at the northern/western most end of the polygon.

**E2a.** At the **southern/eastern** most end of the polygon take photos at the **inner boundary (water's edge)** looking **OUT** of and **INTO** the polygon. Identify the photo numbers and then enter a description of each photograph taken at the southern/eastern most end of the polygon.

**E2b.** At the **southern/eastern** most end of the polygon take photos at the **outer boundary (inland)** looking **OUT** of and **INTO** the polygon. Identify the photo numbers and then enter a description of each photograph taken at the southern/eastern most end of the polygon

**E3.** Take additional photos, as needed to illustrate key features or problems within the polygon. For each "additional" photo, enter the UTM location coordinates and identify each one with its photo number and description.

**E3b.** Additional photo page entered. Answer "Yes" or "No." If additional photos taken exceed space on the field form they will be entered on an additional photo page and entered into the database in this manner. This includes additional photos taken outside of polygon (i.e., non-polygon photos). For each additional photo taken record the waypoint name, enter the UTM location coordinates and identify each photo with its photo number and description.

**E4a, b.** Indicate if there is another polygon adjacent to the **north/west** of this one and identify its polygon name.

**E5a, b.** Indicate if there is another polygon adjacent to the **south/east** of this one and identify its polygon name.

**E6.** Record the type of film (digital or film), film speed or digital quality (dpi), camera lens size, and lens focal length range or magnification, Lens filter used (polarizer or none).

## FACTORS FOR ASSESSING LENTIC WETLAND HEALTH (SURVEY)

Some factors on the evaluation will not apply on all sites. For example, sites without potential for woody species are not rated on factors concerning trees and shrubs. Vegetative site potential can be determined by using a key to site type (e.g., Thompson and Hansen 2001, 2002, 2003, or another appropriate publication). On severely disturbed sites, vegetation potential can be difficult to determine. On such sites, clues to potential may be sought on nearby sites with similar landscape position.

Most of the factors rated in this evaluation are based on ocular estimations. Such estimation may be difficult on large, brushy sites where visibility is limited, but extreme precision is not necessary. While the rating categories are broad, evaluators do need to calibrate their eye with practice. It is important to remember that a health rating is not an absolute value. The factor breakout groupings and point weighting in the evaluation are somewhat subjective and are not grounded in quantitative science so much as in the collective experience of an array of riparian scientists, range professionals, and land managers.

The evaluator must keep in mind that this assessment form is designed to account for most sites and conditions in the applicable region. However, rarely will all the questions seem exactly to fit the circumstances on a given site. Therefore, try to answer each question with a literal reading. If necessary, explain anomalies in the comment section. Each factor below will be rated according to conditions observed on the site. The evaluator will estimate the scoring category and enter that value on the score sheet.

**1. Vegetative Cover of the Polygon.** Around lentic water bodies vegetation cover helps to stabilize shorelines, control nutrient cycling, reduce water velocity, provide fish cover and food, trap sediments, reduce erosion, reduce the rate of evaporation (Platts and others 1987), and contributes primary production to the ecosystem. This question focuses on how much of the entire polygon area is covered by standing plant growth. Item 8 below assesses the amount of human-caused bare ground. Although there is some overlap between these two items, the bare ground to be counted in item 8 is strictly limited in definition, whereas all unvegetated area not inundated by water is counted in this item. The only area within the polygon exempt from consideration is area covered by water, including water between emergent plants such as cattails and bulrushes. Areas such as boat docks, hardened pathways, and artificial structures are counted as unvegetated along with any bare ground, downed wood, and other plant litter. The rationale is that all such unvegetated areas contribute nothing to several of the important lentic wetland functions.

The evaluator is to estimate the fraction of the polygon covered by plant growth. Vegetation cover is ocularly estimated using the canopy cover method (Daubenmire 1959). **NOTE:** For field determination of vegetative cover include **all rooted plant material** (live or dead). Do not include fallen wood or other plant litter. Do not consider the polygon area covered by water (such as between emergent plants).

### Scoring:

**6** = More than 95% of the polygon area is covered by rooted plant material (live or dead).

**4** = 85% to 95% of the polygon area is covered by rooted plant material (live or dead).

**2** = 75% to 85% of the polygon area is covered by rooted plant material (live or dead).

**0** = Less than 75% of the polygon area is covered by rooted plant material (live or dead).

**2. Invasive Plant Species (Weeds).** Invasive plants (weeds) are alien species whose introduction does or is likely to cause economic or environmental harm. Whether the disturbance that allowed their establishment is natural or human-caused, weed presence indicates a degrading ecosystem. While some of these species may contribute to some riparian functions, their negative impacts reduce overall site health. This item assesses the degree and extent to which the site is infested by invasive plants. The severity of the problem is a function of the density/distribution (pattern of occurrence), as well as canopy cover (abundance) of the weeds. In determining the health score, all invasive plant species are considered collectively, not individually. A weed list should be used that is standard for the locality and that indicates which species are being considered (i.e., *Invasive Weed and Disturbance-caused Undesirable Plant List* [Cows and Fish 2002]). Some common invasive plant species are listed on the form, and space is allowed for recording others. Include both woody and herbaceous invasive plant species. **Leave no listed species field blank, however;** enter 0 to indicate absence of a value. (A blank field means the observer forgot to collect the data; a value means the observer looked.)

The site's health rating on this item combines two factors: weed density/distribution class and total canopy cover. A perfect score of 6 out of 6 points can only be achieved if the site is weed free. A score of 4 out of the 6 points means the weed

problem is just beginning (i.e., very few weeds and small total canopy cover [less than 1%]). A moderate weed problem gets 2 out of 6 points. It has a moderately dense weed plant distribution (a class between 4 and 7) and moderate total weed canopy cover (between 1% and 15%). A site scores 0 points if the density/distribution is in class 8 or higher, or if the total weed canopy cover is 15% or more.

**2a. Total Canopy Cover of Invasive Plant Species (Weeds).** The observer must evaluate the total percentage of the polygon area that is covered by the combined canopy of all plants of all species of invasive plants. Determine which rating applies in the scoring scale below. **NOTE:** For field determination of vegetative cover include **all rooted plant material** (live or dead). Do not include fallen wood or other plant litter. Do not consider the polygon area covered by water (such as between emergent plants).

**Scoring:**

- 3 = No invasive plant species (weeds) on the site.
- 2 = Invasive plants present with total canopy cover less than 1% of the polygon area.
- 1 = Invasive plants present with total canopy cover between 1 and 15% of the polygon area.
- 0 = Invasive plants present with total canopy cover more than 15% of the polygon area.

**2b. Density/Distribution Pattern of Invasive Plant Species (Weeds).** The observer must pick a category of pattern and extent of invasive plant distribution from the chart below (Figure 2) that best fits what is observed on the polygon, while realizing that the real situation may be only roughly approximated at best by any of these diagrams. Choose the category that most closely matches the view of the polygon.

**Scoring:**

- 3 = No invasive plant species (weeds) on the site.
- 2 = Invasive plants present with density/distribution in categories 1, 2, or 3.
- 1 = Invasive plants present with density/distribution in categories 4, 5, 6, or 7.
- 0 = Invasive plants present with density/distribution in categories 8, or higher.

CLASS	DESCRIPTION OF ABUNDANCE	DISTRIBUTION PATTERN
0	No invasive plants on the polygon	
1	Rare occurrence	•
2	A few sporadically occurring individual plants	•   •   •
3	A single patch	•••
4	A single patch plus a few sporadically occurring plants	•••   •   •   •
5	Several sporadically occurring plants	•   •   •   •   •
6	A single patch plus several sporadically occurring plants	•••   •   •   •   •
7	A few patches	•••   •••   •••
8	A few patches plus several sporadically occurring plants	•••   •••   •   •   •   •
9	Several well spaced patches	•••   •••   •••   •••
10	Continuous uniform occurrence of well spaced plants	••••••••••••••••••••
11	Continuous occurrence of plants with a few gaps in the distribution	••••••••••••••••••••
12	Continuous dense occurrence of plants	••••••••••••••••••••
13	Continuous occurrence of plants associated with a wetter or drier zone within the polygon.	••••••••••••••••••••

**Figure 2.** Invasive plant species class guidelines (figure adapted from Adams and others [2003])

**NOTE:** Prior to the 2001 season, the health score for weed infestation was assessed from a single numerical value that does not represent weed canopy cover, but instead represents the fraction of the polygon area on which weeds had a well established population of individuals (i.e., the area infested).

**3. Disturbance-Increaser Undesirable Herbaceous Species.** A large cover of disturbance-increaser undesirable herbaceous species, native or exotic, indicates displacement from the potential natural community (PNC) and a reduction in riparian health. These species generally are less productive, have shallow roots, and poorly perform most riparian functions. They usually result from some disturbance that removes more desirable species. Invasive plant species considered in the previous item are not reconsidered. As in the previous item, the evaluator should state the list of species considered. A partial list of undesirable herbaceous species appropriate for use in Alberta follows. A list should be used that is standard for the locality and that indicates which species are being considered (i.e., *Invasive Weed and Disturbance-caused Undesirable Plant List* [Cows and Fish 2002]). The evaluator should list any additional species included.

<i>Antennaria</i> species (pussy-toes)	<i>Hordeum jubatum</i> (foxtail barley)	<i>Potentilla anserina</i> (silverweed)
<i>Brassicaceae</i> (mustards)	<i>Plantago</i> species (plantains)	<i>Taraxacum</i> species (dandelion)
<i>Bromus inermis</i> (awnless brome)	<i>Poa pratensis</i> (Kentucky bluegrass)	<i>Trifolium</i> species (clovers)
<i>Fragaria</i> species (strawberries)	_____	_____
_____	_____	_____

**NOTE:** For field determination of vegetative cover include *all rooted plant material* (live or dead). Do not include fallen wood or other plant litter. Do not consider the polygon area covered by water (such as between emergent plants).

**Scoring:**

- 3** = Less than 5% of the site covered by disturbance-increaser undesirable herbaceous species.
- 2** = 5% to 25% of the site covered by disturbance-increaser undesirable herbaceous species.
- 1** = 25% to 50% of the site covered by disturbance-increaser undesirable herbaceous species.
- 0** = More than 50% of the site covered by disturbance-increaser undesirable herbaceous species.

**4. Preferred Tree and Shrub Establishment and/or Regeneration.** (Skip this item if the site lacks potential for trees or shrubs; for example, the site is a herbaceous wet meadow or marsh.) Not all riparian areas can support trees and/or shrubs. However, on those sites where such species do belong, they play important roles. The root systems of woody species are excellent bank stabilizers, while their spreading canopies provide protection to soil, water, wildlife, and livestock. Young age classes of woody species are important for the continued presence of woody communities not only at a given point in time but into the future. Woody species potential can be determined by using a key to site type (Thompson and Hansen 2001, 2002, 2003). On severely disturbed sites, the evaluator should seek clues to potential by observing nearby sites with similar landscape position. (**NOTE:** Vegetation potential is commonly underestimated on sites with a long history of disturbance.)

When working in areas south of and including the Red Deer River Valley, do not count asexual regeneration from root sprouts on cottonwood trees (*Populus* species other than *P. tremuloides* [aspens]). In this southern area of the province, count only reproduction from seed. This is because these trees are primarily riverine species that pioneer on recent alluvium from seed, and root sprouts do not serve well to maintain populations. In areas north of the Red Deer River Valley (and some areas farther south in higher precipitation zones, such as the foothills west of Highway 2) count any mode of reproduction for this group of trees, because in these cooler/moister zones cottonwoods and balsam poplar populations are not dependent on seed deposited on riverine alluvium.

The following species are excluded from the evaluation (those not listed are considered preferred):

- *Artemisia cana* (silver sagebrush), including subsp. *cana* and *viscidula*;
- *Artemisia frigida* (fringed sagewort);
- *Caragana* species [caragana]
- *Crataegus* species (hawthorn);
- *Elaeagnus angustifolia* (Russian olive);
- *Elaeagnus commutata* [silverberry/wolf willow];
- *Potentilla fruticosa* [shrubby cinquefoil];
- *Rhamnus catharticus* [European/common buckthorn]
- *Rosa* species (rose);
- *Sarcobatus vermiculatus* (greasewood);
- *Symphoricarpos* species [buckbrush/snowberry];
- *Tamarix* species (salt cedar); and
- non-native species.

These are species that may reflect long-term disturbance on a site, that are generally less palatable to browsers, and that tend to increase under long-term moderate-to-intense grazing pressure; **AND** for which there is rarely any problem in maintaining presence on site. Examples of the latter include *Artemisia cana* (silver sagebrush) and *Sarcobatus vermiculatus* (greasewood). Both are considered climax species in many riparian situations and rarely have any problem maintaining a presence on a site. Only under extreme long-term grazing pressures will these species be eliminated from a site. *Elaeagnus angustifolia* (Russian olive), *Caragana* species (caragana), *Rhamnus catharticus* [European/common buckthorn], and *Tamarix* species [salt cedar] are considered especially aggressive, undesirable exotic plants.

The main reason for excluding these plants is that they are far more abundant on many sites than are species of greater concern (i.e., *Salix* species [willows], *Cornus stolonifera* [red-osier dogwood], *Amelanchier alnifolia* [Saskatoon serviceberry], and many other taller native riparian species), and they may mask the ecological significance of a small amount of a species of greater concern. **FOR EXAMPLE:** A polygon may have *Symphoricarpos occidentalis* (buckbrush/snowberry) with 30% canopy cover showing young plants for replacement of older ones, while also having a trace of *Salix exigua* (sandbar willow) present, but represented only by older mature individuals. We feel that the failure of the willow to regenerate (even though there is only a small amount) is very important in the health evaluation, but by including the buckbrush/snowberry and willow together on this polygon, the condition of the willow would be hidden (overwhelmed by the larger amount of buckbrush/snowberry).

For shrubs in general, seedlings and saplings can be distinguished from mature plants as follows. For those species having a mature height generally over 1.8 m (6.0 ft), seedlings and saplings are those individuals less than 1.8 m (6.0 ft) tall. For species normally not exceeding 1.8 m (6.0 ft), seedlings and saplings are those individuals less than 0.45 m (1.5 ft) tall or which lack reproductive structures and the relative stature to suggest maturity. Count plants installed by human planting, if these are successfully established; which means they have survived at least one full year after planting. (**NOTE:** Evaluators should take care not to confuse short stature resulting from intense browsing with that due to young plants.)

**Scoring:** (If the site has no potential for trees or shrubs [except for the species listed above to be excluded], replace both Actual Score and Possible Score with NA. If the observer is not fairly certain potential exists for preferred trees or shrubs, then enter NC and explain in the comment field below.)

**6** = More than 15% of the total canopy cover of preferred trees/shrubs is seedlings and/or saplings.

**4** = 5% to 15% of the total canopy cover of preferred trees/shrubs is seedlings and/or saplings.

**2** = Less than 5% of the total canopy cover of preferred tree/shrubs is seedlings and/or saplings.

**0** = Preferred tree/shrub seedlings and saplings absent.

**5a. Browse Utilization of Available Preferred Trees and Shrubs.** (Skip this item if the site lacks trees or shrubs; for example, the site is a herbaceous wet meadow or cattail marsh, or all woody plants have already been removed.) Livestock and/or wildlife browse many riparian woody species. Excessive browsing can eliminate these important plants from the community and result in their replacement by undesirable invaders. With excessive browsing, the plant loses vigour, is prevented from flowering, or is killed. Utilization in small amounts is normal and not a health concern, but concern increases with greater browse intensity.

The following species are excluded from the evaluation:

- *Artemisia cana* (silver sagebrush), including subsp. *cana* and *viscidula*;
- *Artemisia frigida* (fringed sagewort);
- *Caragana* species [caragana]
- *Crataegus* species (hawthorn);
- *Elaeagnus angustifolia* (Russian olive);
- *Elaeagnus commutata* [silverberry/wolf willow];
- *Potentilla fruticosa* [shrubby cinquefoil];
- *Rhamnus catharticus* [European/common buckthorn]
- *Rosa* species (rose);
- *Sarcobatus vermiculatus* (greasewood);
- *Symphoricarpos* species [buckbrush/snowberry];
- *Tamarix* species (salt cedar); and
- non-native species.



These are species that may reflect long-term disturbance on a site, that are generally less palatable to browsers, and that tend to increase under long-term moderate-to-intense grazing pressure; **AND** for which there is rarely any problem in maintaining presence on site. Examples of the latter include *Artemisia cana* (silver sagebrush) and *Sarcobatus vermiculatus* (greasewood). Both are considered climax species in many riparian situations and rarely have any problem maintaining a presence on a site. Only under extreme long-term grazing pressures will these species be eliminated from a site. *Elaeagnus angustifolia* (Russian olive), *Caragana* species (caragana), *Rhamnus catharticus* [European/common buckthorn], and *Tamarix* species [salt cedar] are considered especially aggressive, undesirable exotic plants.

As discussed above, the main reason for excluding these plants is they are far more abundant on many sites than are species of greater concern (e.g., *Salix* species [willows], *Cornus stolonifera* [red-osier dogwood], *Amelanchier alnifolia* [Saskatoon serviceberry], and many other taller native riparian species), and they may mask the ecological significance of a small amount of a species of greater concern. **FOR EXAMPLE:** A polygon may have *Symphoricarpos occidentalis* (buckbrush/snowberry) with 30% canopy cover showing young plants for replacement of older ones, while also having a trace of *Salix exigua* (sandbar willow) present, but represented only by older mature individuals. We feel that the failure of the willow to regenerate (even though there is only a small amount) is very important in the health evaluation, but by including the buckbrush/snowberry and willow together on this polygon, the condition of the willow would be hidden (overwhelmed by the larger amount of buckbrush/snowberry).

Consider as available all tree and shrub plants to which animals may gain access and that they can reach. For tree species, this means mostly just seedling and sapling age classes. When estimating degree of utilization, count browsed second year and older leaders on representative plants of woody species normally browsed by ungulates. Do not count current year's use, because this would not accurately reflect actual use when more browsing can occur later in the season. Browsing of second year or older material affects the overall health of the plant and continual high use will affect the ability of the plant to maintain itself on the site. Determine percentage by comparing the number of leaders browsed or utilized with the total number of leaders available (those within animal reach) on a representative sample (at least three plants) of each tree and shrub species present. Do not count utilization on dead plants, unless it is clear that death resulted from over-grazing. **NOTE:** If a shrub is entirely mushroom/umbrella shaped by long term intense browse or rubbing, count utilization of it as heavy.

**Scoring:** (Consider all shrubs within animal reach and seedlings and saplings of tree species. If the site has no woody vegetation [except for the species listed above to be excluded], replace both Actual Score and Possible Score with NA.)

**3** = None (0% to 5% of available second year and older leaders of preferred species are browsed).

**2** = Light (5% to 25% of available second year and older leaders of preferred species are browsed).

**1** = Moderate (25% to 50% of available second year and older leaders of preferred species are browsed).

**0** = Heavy (More than 50% of available second year and older leaders of preferred species are browsed).

**5b. Live Woody Vegetation Removal by Other Than Browsing.** Excessive cutting or removing parts of plants or whole plants by agents other than browsing animals (e.g., human clearing, cutting, beaver activity, etc.) can result in many of the same negative effects to the community that are caused by excessive browsing. However, other effects from this kind of removal are direct and immediate, including reduction of physical community structure and wildlife habitat values. **Do not include natural phenomena such as natural fire, insect infestation, etc. in this evaluation.**

Removal of woody vegetation may occur at once (a logging operation), or it may be cumulative over time (annual firewood cutting or beaver activity). This question is not so much to assess long term incremental harvest, as it is to assess the extent that the stand is lacking vegetation that would otherwise be there today. Give credit for re-growth. Consider how much the removal of a tree many years ago may have now been mitigated with young replacements.

Four non-native species or genera are excluded from consideration because these are aggressive, invasive exotic plants that should be removed. They are *Elaeagnus angustifolia* (Russian olive), *Rhamnus cathartica* (common buckthorn), *Caragana arborescens* (common caragana), and *Tamarix* species (salt cedar).

Determine the extent to which woody vegetation (trees and shrubs) is lacking due to being physically removed (i.e., cut, mowed, trimmed, logged, cut by beaver, or otherwise removed from their growing position). The timeframe is less important than the ecological effect. Time to recover from this kind of damage can vary widely with site characteristics. The objective is to measure the extent of any damage remaining **today** to the vegetation structure resulting from woody removal. We expect that the woody community will recover over time (re-grow), just as an eroding bank will heal with re-growing plant roots. This question simply asks how much woody material is still missing from what should be on the site? The amount of time

since removal doesn't really matter, if re-growth has been allowed to progress. If 20 years after logging, the site has a stand of sapling spruce trees, then it should get partial re-growth credit, but not full credit, since the trees still lack much of their potential habitat and ecological value. (**NOTE:** In general, the more recent the removal, the more entirely it should be fully counted; and conversely, the older the removal, the more likely it will have been mitigated by re-growth.)

This question is really looking at volume (three dimensions) and not canopy cover (two dimensions). For example, if an old growth spruce tree is removed, a number of new seedlings/saplings may become established and could soon achieve the same canopy cover as the old tree had. However, the value of the old tree to wildlife and overall habitat values is far greater than that of the seedling/saplings. It will take a very long time before the seedlings/saplings can grow to replace all the lost habitat values that were provided by the tall old tree. On the other hand, shrubs, such as willows, grow faster and may replace the volume of removed plants in a much shorter time. Answer this question by estimating the percent of woody material that is missing from the site due to having been removed by human action. Select a range category from the choices given that best represents the percent of missing woody material.

**Scoring:** (*If the site has no trees or shrubs AND no cut plants or stumps of any trees or shrubs [except for the species listed above to be excluded], replace both Actual Score and Possible Score with NA.*)

**3** = None (0% to 5% of live woody vegetation expected on the site is lacking due to cutting).

**2** = Light (5% to 25% of live woody vegetation expected on the site is lacking due to cutting).

**1** = Moderate (25% to 50% of live woody vegetation expected on the site is lacking due to cutting).

**0** = Heavy (More than 50% of live woody vegetation expected on the site is lacking due to cutting).

**6. Human Alteration of Polygon Vegetation Community Composition.** Human alteration of the vegetation is meant to include all changes to the plant community composition or structure on the polygon from human causes (e.g., logging, mining, roads, construction, or development) or by agents of human management (e.g., livestock). ***It is not meant to include transitory or short-term removal of plant material that does not alter long term plant community composition*** (i.e., grazing at carefully managed levels or wood cutting that does not change long term species composition of the community). Also include impacts caused by extreme concentrations of managed wildlife, rationale being that wildlife concentrations great enough to cause significant site damage are usually the result of human management choices. Beaver activities that alter vegetative communities will not be included in this question, but are included in the utilization question.

Of concern are the kinds of change that diminish or disrupt the natural wetland function of the vegetation. These include, but are not limited to, conversion of natural communities to lawns or hayfields (but not the actual mowing), changing plant community composition (e.g., causing replacement of willows with rose and buckbrush, woody species with herbaceous species, etc.), replacing native plants with tame plants, replacing deep rooted plants with shallow rooted plants, and/or replacing tall species with short species. In a case where the vegetation community is altered, due to removal of woody cover that allows conversion to a long term cover of a different kind of vegetation (i.e., cottonwoods/poplars are cut, and the site changes to a *Poa pratensis* [Kentucky bluegrass] cover), then the polygon gets a low score for both woody vegetation removal and for alteration of the vegetation community. **Note:** Only consider invasion by non native species as human caused alteration when there is clear visible evidence of human management cause. Do not count the invasion as human caused alteration if it is due to natural cause (such as wind blown seed) that is independent of land use or management action.

On polygons adjacent to water, remember that the polygon extends out to where the water is two metres deep. (**NOTE:** Do not count the same area twice by including it as both a vegetative and a physical alteration, unless there clearly are both kinds of alteration. Decide into which category a particular effect should go. For example: A timber harvest may clear vegetation, but not necessarily cause physical damage on one area; while on another area it may cause both clearing of vegetation and disruption of the soil by heavy equipment.)

**Scoring:**

**6** = Less than 5% of polygon vegetation community composition is altered by human activity.

**4** = 5% to 15% of polygon vegetation community composition is altered by human activity.

**2** = 15% to 35% of polygon vegetation community composition is altered by human activity.

**0** = 35% or more of polygon vegetation community composition is altered by human activity.

**7. Human Alteration of Polygon Physical Site.** The purpose of this question is to assess physical change to the soil, bank/shore integrity, hydrology, etc. as it affects the ability of the natural system to function normally. Changes in shore and bank contour and any change in soil structure will alter infiltration of water, increase soil compaction, and cause increased

sediment contribution to the water body. Every human activity in or around a natural site can alter that site. This question seeks to assess the accumulated effects of all human-caused change.

Include all changes to the physical attributes of the site caused by human actions (e.g., logging, mining, housing development) or by agents of human management (e.g., livestock) and also any effects from concentrated wildlife use (Rationale being that wildlife concentrations great enough to cause significant site damage are usually the result of human management activities.) The kinds of physical change that diminish or disrupt the natural wetland functions on the site include, but are not limited to, hummocking, pugging, animal trails (livestock or wildlife), human roads, trails, buildings, landscaping, boat launches/docks, beach clearing and building, or rip-rapping of shores and banks. (**NOTE: Do not count the same area twice by including it as both a vegetative and a physical alteration, unless there clearly are both kinds of alteration. Decide into which category a particular effect should go.**) For example: A cottage owner may clear vegetation to gain a view of the lake without causing physical damage to one area; whereas, if he/she hauls in sand to enhance the beach, there is also physical alteration of the same site.) This item is scored in two parts:

**7a. Estimate the percentage of the polygon that is altered by human activities.**

**Scoring:**

- 12** = Less than 5% of the polygon is physically altered by human activity.
- 8** = 5% to 15% of the polygon is physically altered by human activity.
- 4** = 15% to 35% of the polygon is physically altered by human activity.
- 0** = More than 35% of the polygon is physically altered by human activity.

**7b. Estimate the severity of the alteration, without regard to the portion of the polygon it might occupy.** Full score is given only to polygons with no physical alteration by human activity. Four categories of alteration severity are described in terms of change to the site vegetation and hydrologic function. (**NOTE: This call uses vegetation change to indicate degree of alteration, as a signal of physical alteration, but the alteration must be physical in nature, not just vegetative change alone; e.g., disruption of soil, hydrology (including infiltration/interception of water), topography, etc.**)

Document the call with photos and commentary. Categories of severity of human-caused physical alteration are described below with conceptual guidelines. These guidelines are not comprehensive, but are intended as a relative scale by which the observer can judge his/her site. Every case is different, and there is no absolute measuring stick to apply. Use the following comparative descriptions to choose a category of alteration on your site:

- **None**—No human-caused physical alteration observed on the polygon.
- **Slight**—Physical site integrity is near natural. Human-caused alteration (including recovery from any past severe alterations) is apparent, but reflects minimal impact to plant communities and hydrological function in the altered areas (e.g., the plant community is little changed from that on nearby sites lacking physical alteration; any pugging and hummocking or other disruption of the soil profile is relatively shallow and is well vegetated with appropriate species).
- **Moderate**—As compared with nearby unaltered sites, human-caused physical alteration on the polygon (including recovery from any past severe alterations) has noticeably altered the physical site integrity to the point that plant communities and hydrological function on the altered areas show visible impact. The plant community differs noticeably (by having introduced or missing components) from nearby sites that are on similar landscape position and that lack physical alterations. Pugging and hummocking or other disruption of the soil profile is moderate in depth and height of hummocks. Such alteration is either becoming re-vegetated with appropriate species, or is well covered with a mix of less desirable and appropriate species.
- **Severe**—Human-caused physical site alteration on the polygon has compromised the physical integrity of the altered areas (even if only a small area is altered). Old alterations have not recovered and are still affecting the vegetation or hydrological functions (e.g., the plant community differs radically from nearby sites in similar position that lack physical alterations, reflecting altered hydrologic and/or soil conditions). Pugging and hummocking or other disruption of the soil profile is severe in depth of disturbance and/or height of hummocking. Alterations remain mostly bare of plant cover, or are becoming vegetated with invasive or undesirable species.

**Scoring:**

- 3** = **No physical alterations** to the site by human activity.
- 2** = Human alterations to the physical site are **slight** in effect.
- 1** = Human alterations to the physical site are **moderate** in effect.
- 0** = Human alterations to the physical site are **severe** in effect.

**8. Human-Caused Bare Ground.** Bare ground is exposed soil surface (not covered by plants, litter or duff, down wood, or rocks larger than 6 cm [2.5 in]). Hardened, impervious surfaces (e.g., asphalt, concrete, etc.) are not bare ground—these do not erode nor allow weeds sites to invade. Bare ground may result naturally from several processes (i.e., sedimentation, flood erosion, fire, tree fall, and exposure of lakebed by low water level), but that caused by human activity always indicates an impairment of wetland health. Exposed soil is vulnerable to erosion and is where weeds become established. Bare soil is not producing, nor providing habitat. Sediment deposits and other natural bare ground are excluded as normal and probably beyond management control. Human land uses often causing bare ground include livestock grazing, recreation, off road vehicle use, and resource extraction activities. After considering the causes of all bare ground on the site, the evaluator must estimate what percent of the site (polygon) area is human-caused bare ground.

**Scoring:**

**6** = Less than 1% of the polygon is human-caused bare ground.

**4** = 1% to 5% of the polygon is human-caused bare ground.

**2** = 5% to 15% of the polygon is human-caused bare ground.

**0** = 15% or more of the polygon is human-caused bare ground.

**9. Degree of Artificial Withdrawal or Raising of Water Level.** Although water levels naturally fluctuate on a seasonal basis in most systems, many wetland systems are affected by human-caused (artificial) additions or withdrawals. This artificial changes of water level rarely follow a temporal regime that maintains healthy native wetland plant communities. The result is often a barren band of shore exposed or inundated for much of each growing season. This causes shore material to destabilize, and often provides sites for weeds to invade. Such conditions are extremely detrimental to healthy riparian function.

Not all lentic wetlands evaluated with this form will have surface water potential, but any wetland may have its water table degraded by draining, pumping, or diverting its surface or subsurface supply. On such lentic wetlands as marshes and wet meadows, look for evidence of drainage ditching, pumping, and the interruption of normal surface drainage inputs by livestock watering dugouts, cross slope ditches, or dams upslope.

In this item the evaluator is asked to categorize the degree to which the system is subjected to artificially rapid or unnaturally timed fluctuations in water level. Reservoirs intended for storage of water for power generation, irrigation, and/or livestock watering typically exhibit the most severe effects, but water may be diverted or pumped from natural systems for many other reasons (domestic use, industrial use, livestock watering, etc.). This item requires the evaluator to make a subjective call by choosing as a best fit one of the categories of drawdown severity described below. (**NOTE:** Be careful to consider the scale of the water body as it relates to the scale of change. Pumping a small dugout full of water for livestock might severely impact a 0.8 ha (2 ac) slough, but be negligible to a lake covering a section of land.)

Be sure to document the grounds for your estimate. If there is no way to know with any reasonable degree of certainty how much water is being added or removed, it may be better to describe the situation and to zero out this item (not answer it). During periods of drought lakebeds become exposed, and often exhibit wide zones of almost barren shore. ***The evaluator must be careful not to attribute this natural phenomenon unfairly to a human activity.***

---

**Severity Categories of Lentic Water Level Manipulation**

---

<b>Not Subjected</b>	The water body, or wetland, is not subjected to artificial water level change (e.g., drawdown, addition, stabilization, etc.). This category may include very small amounts of change that cause no detectible fluctuation in water level.
<b>Minor</b>	The water body or wetland is subject to no more than minor artificial water level change. The shore area remains vegetated, and withdrawal of water is limited or slow enough that vegetation is able to maintain growth and prevent soil exposure. A relatively narrow band affected by the water level fluctuation may support only annual plants.
<b>Moderate</b>	The water body or wetland is subject to moderate quantities, speed and/or frequency of artificial water level change. Where water is removed, it is done in a way that allows pioneer plants to vegetate at least half of the exposed area resulting from drawdown. Where water is added, some flooding may occur at levels or times not typical to the area/season.
<b>Extreme</b>	The water body or wetland is subjected to extreme changes in water level due to volume (extent), speed and/or frequency of artificial water addition or removal. Frequent or unnatural levels of flooding occur where water is added, including

extensive flooding into riparian and/or upland areas; or no natural annual drawdown is allowed to occur. In extreme artificial drawdown situations, a wide band of exposed bottom remains unvegetated.

**Scoring:**

**9** = The water body, or wetland, is *not subjected* to artificial water level change.

**6** = The degree of artificial water level change is *minor*.

**3** = The degree of artificial water level change is *moderate*.

**0** = The degree of artificial water level change is *extreme*.

**Calculating the Lentic Health Score**

To arrive at the overall site health rating, the scores are totaled for all the factors, and that total is divided by the possible perfect score total. A sample score sheet is shown below.

<b>Vegetation Factors</b>	<b>Actual Pts</b>	<b>Possible Pts</b>
1. Vegetative Cover of Polygon	6	6
2a. Total Canopy Cover of Invasive Plant Species (Weeds)	1	3
2b. Density/Distribution Pattern of Invasive Plant Species (Weeds)	1	3
3. Disturbance-Increaser Undesirable Herbaceous Species	2	3
4. Preferred Tree and Shrub Establishment and/or Regeneration	2	6
5a. Browse Utilization of Available Preferred Trees and Shrubs	2	3
5b. Live Woody Vegetation Removal by Other Than Browsing	3	3
6. Human Alteration of Polygon Vegetation Community Composition	<u>4</u>	<u>6</u>
<b>Vegetative Score:</b>	<b>21</b>	<b>33</b>
<b>Soil/Hydrology Factors</b>		
7a. Percent of Polygon Physical Site Altered by Human Activities	8	12
7b. Severity of Human-Caused Alteration of Polygon Physical Site	2	3
8. Human-Caused Bare Ground	2	6
9. Degree of Artificial Withdrawal or Raising of Water Level	<u>9</u>	<u>9</u>
<b>Soil/Hydrology Score:</b>	<b>21</b>	<b>30</b>
<b>TOTAL SCORE:</b>	<b>42</b>	<b>63</b>

**Health Rating Formula:** Health Rating = (Total Actual Score) / (Total Possible Score) X 100%

$$\text{Health Rating} = (42) / (63) \times 100\% = 67\%$$

**Health Category:** 80 to 100% = Proper Functioning Condition (Healthy)  
60 to less than 80% = Functional At Risk (Healthy, but with Problems)  
Less than 60% = Nonfunctional (Unhealthy)

A manager should realize that a less than perfect score is not necessarily cause for concern. An area rated at 80% is still considered to be functioning properly. At the same time, ratings of individual factors can be useful in detecting strengths or weaknesses of a site. A low score on any factor warrants management focus. For example, the sample score sheet shown above has low scores for invasive plant species, tree and shrub regeneration, and bare ground (items 2, 4, and 8). These are factors in which a management change might result in improvement on a subsequent assessment.

## ADDITIONAL MANAGEMENT CONCERNS

The following items do not contribute to a site's health assessment rating. Rather, they may help to quantify inherent physical site characteristics that reveal structural weaknesses or sensitivities or to assess the direction of change on a site. These data can be useful for planning future site management.

**10a. Polygon Trend.** Select the *one category* (Improving, Degrading, Static, or Trend Unknown) that best indicates the current trend on the polygon. Trend refers, in the sense used here, not specifically to successional pathway change, but in a more general sense of apparent community health. By definition, trend implies change over time. Accordingly, a trend analysis would require comparison of repeated observations over time. However, some insights into trend can be observed in a single visit. For example, the observer may notice healing (revegetating) of a degraded shoreline and recent establishment of woody seedlings and saplings. This would indicate changing conditions that suggest an improving trend. If such indicators are not apparent, enter the category status unknown.

**10b.** Has management influenced trend? Answer "Yes," "No," "Unknown," "NC," or "NA." *Only use NA if you answered "Status Unknown" to 10a.*

**10c.** Describe how the management change influenced the parameters to change and justify/explain your answer. *Answer "NA" if the polygon is "Status Unknown" (10a).*

**11. Overflow Structure Stability.** Often the most dynamically unstable point in a lentic system is at the overflow, or outlet. Natural systems usually evolve behind a relatively stable outlet structure, but the overflow structures, or spillways, of human-made water bodies often become unstable and erode, wash out, or downcut causing severe disruption to the lentic system dependent on that body of water. Indicate where on the water body the overflow structure is located, even if it is not within the polygon.

**Scoring:** (If the water body is not human constructed nor structurally altered, and lacks an overflow structure, replace both Actual and Possible Scores with NA.)

**6** = The overflow structure is made of concrete, pipe, or armoured rock and appears stable.

**4** = The overflow structure is unprotected or is made of other material, but still appears stable.

**2** = The overflow structure is made of concrete, pipe, or armoured rock, but appears unstable.

**0** = The overflow structure is unprotected or is made of other material and appears unstable.

**12. Shoreline Rock Volume and Size.** The composition of shoreline materials influences the susceptibility of the shoreline to erosion caused by trampling, wave action, or other disturbance. In general, larger rocks provide better protection against disturbance than smaller materials. Thus, shoreline composed primarily of silts and clays—characteristic of many lentic systems in the Great Plains—require more vegetative protection to compensate for the smaller particle sizes.

**12a. Shoreline Rock Volume.** Rate the shoreline rock volume as the highest appropriate of the following categories:

**Scoring:**

**3** = More than 40% of shoreline volume is rocks at least 6.4 cm (2.5 in).

**2** = 20% to 40% of shoreline volume is rock at least 6.4 cm (2.5 in).

**1** = 10% to 20% of shoreline volume is rock at least 6.4 cm (2.5 in).

**0** = Less than 10% of shoreline volume is rocks at least 6.4 cm (2.5 in).

**12b. Shoreline Rock Size.** Rate the shoreline rock size for the polygon as the highest appropriate of the following categories:

**Scoring:**

**3** = At least 50% of rocks present are boulders and large cobbles (>13 cm [5 in]).

**2** = 50% of rocks present are small cobbles and larger (>6.4 cm [2.5 in]).

**1** = At least 50% of rocks present are coarse gravels and larger (>1.5 cm [0.6 in]).

**0** = Less than 50% of rocks present are coarse gravels and larger (>1.5 cm [0.6 in]).

**13. Vegetation Use by Animals.** Record the rating category, which best describes the vegetation use by animals (Platts and others, 1987).

---

Code	Category Description
------	----------------------

---

<b>0% to 25%</b>	Vegetation use is light or none. Almost all plant biomass at the current development stage remains. Vegetative cover is close to that which would occur without use. Unvegetated areas (such as bedrock) are not a result of land uses.
<b>26% to 50%</b>	Vegetation use is moderate. At least half the potential plant biomass remains. Average stubble height is more than half its potential at the present stage of development.
<b>51% to 75%</b>	Vegetation use is high. Less than half the potential plant biomass remains. Plant stubble height is usually more than 5 cm (2 in) (on many ranges).
<b>76% to 100%</b>	Vegetation use is very high. Only short stubble remains (usually less than 5 cm [2 in] on many ranges). Almost all plant biomass has been removed. Only the root systems and parts of the stems remain.

---

**14. Susceptibility of Parent Material to Erosion.** The soils derived from shale or having a large clay content are highly susceptible to compaction and trampling when wet. There is evidence that trampling by hooves and subsequent loss of herbaceous vegetation when soils are wet are major contributions to site degradation. In contrast, those sites having soils derived from sandstone or any of the hard metamorphosed rock found in the Rocky Mountains commonly have a fine sandy loam to loam texture and are more resistant to damage when wet. Intermediate of these soils are those having textures of clay loam to loam. Texturing the soil by the ribboning technique or by feel will be required for this determination. Rate the polygon soil according to one of these categories based on indicators as described above.

**Scoring:**

- 3** = Not susceptible to erosion (well armoured).
- 2** = Slightly susceptible to erosion (moderately armoured).
- 1** = Moderately susceptible to erosion.
- 0** = Extremely susceptible to erosion.

**15. Percent of Shoreline Accessible to Large Animals.** Record the percent of shoreline length accessible to large hoofed animals (livestock and wildlife). In general, only consider topography (steep banks, deep water, etc.) and dense vegetation as restricting access. Fences, unless part of an enclosure, do not necessarily restrict livestock access even though they may appear to be doing so at the time.

**16. Quantify the Percent of Tree and Shrub Cover in the Polygon that is Dead and/or Decadent.** A decadent plant is one having at least 30% of its upper canopy dead. Dead lower branches are not a problem if the upper canopy is vigorous.

**17. Break Down the Polygon Area into the Land Uses Listed. Name any Others Observed.**

**18. Break Down the Area Adjacent to the Polygon into the Land Uses Listed. Name any Others Observed.**

**19. Comments and Observations.** Add any necessary commentary to explain or amplify the data recorded. Do not leave this space blank. Describe any unique characteristics of the site and other observations relating to the vegetation or to the physical conditions of the site. Each item in the health rating has a small space provided for specific information to enlighten the score given. This larger space is the place for more general commentary to help the reader understand the larger context of the data. Such things as landscape setting and local land use history are appropriate.

## LITERATURE CITED

- Adams, Barry and Lorne Fitch. 1995. Caring for the green zone, riparian areas and grazing management. Alberta Riparian Habitat Management Project. Lethbridge, Alberta, Canada. 37p.
- Adams, B. W., G. Ehlert, C. Stone, M. Alexander, D. Lawrence, M. Willoughby, D. Moisey, C. Hincz, and A. Burkinshaw. 2003. Range health assessment for grassland, forest and tame pasture. Public Lands and Forests Division, Alberta Sustainable Resource Development. Publication. No. T/044.
- Alberta Natural Heritage Information Centre. 1999. Natural regions and subregions of Alberta. Internet website: <http://www.gov.ab.ca/env/parks/anhic/abnatreg.html>. Edmonton, Alberta, Canada. T5K 2J6.
- Cooperrider, Allen Y., Raymond J. Boyd, and Hanson R. Stuart. 1986. Inventory and monitoring of wildlife habitat. USDI Bureau of Land Management, Denver Service Center, Denver, Colorado, USA. 858p.
- Cowardin, L. M., V. Carter, F. C. Golet, and E. T. LaRoe. 1979. Classification of wetlands and deep water habitats of the United States. USDI Fish and Wildlife Service, Office of Biological Services, Washington, DC, USA. Publication Number FWS/OBS-79/31. 107p.
- Cows and Fish. 2001. Invasive Weed and Disturbance-caused Herbaceous Species List For Use in Riparian Health Assessment and Inventory in Alberta--draft. Alberta Riparian Habitat Management Program. Lethbridge, Alberta, Canada.
- Daubenmire, R. D. 1959. A canopy-coverage method of vegetation analysis. *Northwest Science* 33:43-66.
- Federal Interagency Committee for Wetland Delineation. 1989. Federal manual for identifying and delineating jurisdictional wetlands. US Army Corps of Engineers, US Environmental Protection Agency, USDI Fish and Wildlife Service, and USDA Soil Conservation Service Cooperative Technical Publication, Washington, DC, USA. 76p.
- Fitch, L., B.W. Adams and G. Hale, Eds. 2001. Riparian Health Assessment for Streams and Small Rivers - Field Workbook. Lethbridge, Alberta: Cows and Fish Program. (adapted from Riparian and Wetland Research Program, School of Forestry. 2001. Lotic health assessments: Riparian Health Assessment for Streams and Small Rivers [Survey] User Guide. University of Montana, Missoula, Montana, USA. January 2001.) 75p.
- Fitch, L. and N. Ambrose. 2003. Riparian areas: A user's guide to health. Lethbridge, Alberta: Cows and Fish Program. ISBN No. 0-7785-2305-5. 46p.
- Hansen, Paul L., Robert D. Pfister, Keith Boggs, Bradley J. Cook, John Joy, and Dan K., Hinckley. 1995. Classification and management of Montana's riparian and wetland sites. Miscellaneous Publication No 54. Montana Forest and Conservation Experiment Station, School of Forestry, University of Montana, Missoula, Montana, USA. 646p.
- Huel, Denis. 1998. Streambank stewardship, your guide to caring for riparian areas in Saskatchewan. ISBN No. 1-896793-20-7. Saskatchewan Wetland Conservation Corporation. Regina, Saskatchewan, Canada. 43p.
- Huel, Denis. 2000. Managing Saskatchewan Wetlands—a landowner's guide. ISBN No. 1-896793-26-6. Saskatchewan Wetland Conservation Corporation. Regina, Saskatchewan, Canada. 68p.
- Mitsch, William J., and James G. Gosselink. 1993. Wetlands. Second Edition. Van Nostrand Reinhold, Publishers, New York, New York, USA. 722p.
- Platts, W. S., C. Armour, G. D. Booth, M. Bryant, J. L. Bufford, P. Cuplin, S. Jensen, G. W. Lienkaemper, G. W. Minshall, S. B. Monsen, R. L. Nelson, J. R. Sedell, and J. S. Tuhy. 1987. Methods for evaluating riparian habitats with applications to management. USDA Forest Service General Technical Report INT-221. Intermountain Research Station, Ogden, Utah, USA. 187p.



- Reed, Porter B., Jr. 1988. National list of plant species that occur in wetlands: Northwest (Region 9). US Fish and Wildlife Service Biological Report 88 (26.9). USDI Fish and Wildlife Service, Research and Development, Washington, DC, USA. 89p.
- Shaw, S. P., and C. G. Fredine. 1956. Wetlands of the United States: Their extent and their value for waterfowl and other wildlife. USDI Fish and Wildlife Service, Circular 39. Washington, DC, USA. 67p.
- Stewart, R. E., and H. A. Kantrud. 1972. Classification of natural ponds and lakes in the glaciated prairie region. USDI Fish and Wildlife Service, Research Publication 92. 57p.
- Thompson, William H. and Paul L. Hansen. 2001. Classification and management of riparian and wetland sites of the Saskatchewan prairie ecozone and parts of adjacent subregions. Saskatchewan Wetland Conservation Corporation. Regina, Saskatchewan, Canada. 298p.
- Thompson, William H. and Paul L. Hansen. 2002. Classification and management of riparian and wetland sites of the Alberta Grassland Natural Region and adjacent subregions. Bitterroot Restoration, Inc. Prepared for the Alberta Riparian Habitat Management Program-Cows and Fish, Lethbridge, Alberta, Canada. 416p.
- Thompson, William H. and Paul L. Hansen. 2003. Classification and management of riparian and wetland sites of Alberta's Parkland Natural Region and Dry Mixedwood Natural Subregion. Bitterroot Restoration, Inc. Prepared for the Alberta Riparian Habitat Management Program-Cows and Fish, Lethbridge, Alberta, Canada. 340p.
- USDA Forest Service. 1989. Ecosystem classification handbook: ECODATA. USDA Forest Service, Northern Region, Missoula, Montana, USA.
- Valastin, Pat, and others. 1999. Caring for Shoreline Properties. Alberta Conservation Association. Edmonton, Alberta, Canada. T5L2W4. 29p.

**LENTIC WETLAND SURVEY HEALTH ASSESSMENT  
FIELD SCORE SHEET**

**1. Vegetative Cover of the Polygon.** Score: \_\_\_\_ / 6

- 6 = More than 95% of the polygon area is covered by live plant growth.
- 4 = 85% to 95% of the polygon area is covered by live plant growth.
- 2 = 75% to 85% of the polygon area is covered by live plant growth.
- 0 = Less than 75% of the polygon area is covered by live plant growth.

**2a. Total Canopy Cover of Invasive Plant Species (Weeds).** Score: \_\_\_\_ / 3

- 3 = No invasive plant species (weeds) on the site.
- 2 = Invasive plants present with total canopy cover less than 1% of the polygon area.
- 1 = Invasive plants present with total canopy cover between 1% and 15% of the polygon area.
- 0 = Invasive plants present with total canopy cover more than 15% of the polygon area.

**2b. Density/Distribution Pattern of Invasive Plant Species (Weeds).** Score: \_\_\_\_ / 3

- 3 = No invasive plant species (weeds) on the site.
- 2 = Invasive plants present with density/distribution in categories 1, 2, or 3.
- 1 = Invasive plants present with density/distribution in categories 4, 5, 6, or 7.
- 0 = Invasive plants present with density/distribution in categories 8, or higher.

**3. Disturbance-Increaser Undesirable Herbaceous Species.** Score: \_\_\_\_ / 3

- 3 = Less than 5% of the site covered by disturbance-increaser undesirable herbaceous species.
- 2 = 5% to 25% of the site covered by disturbance-increaser undesirable herbaceous species.
- 1 = 25% to 50% of the site covered by disturbance-increaser undesirable herbaceous species.
- 0 = More than 50% of the site covered by disturbance-increaser undesirable herbaceous species.

**4. Preferred Tree and Shrub Establishment and/or Regeneration.** Score: \_\_\_\_ / 6

*(If site lacks potential for woody species, replace both Actual and Possible Scores with NA.)*

- 6 = More than 15% of the total canopy cover of preferred trees/shrubs are seedlings and/or saplings.
- 4 = 5% to 15% of the total canopy cover of preferred trees/shrubs is seedlings and/or saplings.
- 2 = Less than 5% of the total canopy cover of preferred tree/shrubs are seedlings and/or saplings.
- 0 = Preferred tree/shrub seedlings and saplings absent.

**5a. Browse Utilization of Available Preferred Trees and Shrubs.** Score: \_\_\_\_ / 3

*(If the site has no woody vegetation [except for the species listed to be excluded], replace both Actual Score and Possible Score with NA.)*

- 3 = None (0% to 5% of available second year and older leaders of preferred species are browsed).
- 2 = Light (5% to 25% of available second year and older leaders of preferred species are browsed).
- 1 = Moderate (25% to 50% of available second year and older leaders of preferred species are browsed).
- 0 = Heavy (More than 50% of available second year and older leaders of preferred species are browsed).

**5b. Live Woody Vegetation Removal by Other Than Browsing** Score: \_\_\_\_ / 3

*(If the site has no trees or shrubs AND no cut plants or stumps of any trees or shrubs [except for the species listed to be excluded], replace both Actual Score and Possible Score with NA.)*

- 3 = None (0% to 5% of live woody vegetation expected on the site is lacking due to cutting).
- 2 = Light (5% to 25% of live woody vegetation expected on the site is lacking due to cutting).
- 1 = Moderate (25% to 50% of live woody vegetation expected on the site is lacking due to cutting).
- 0 = Heavy (More than 50% of live woody vegetation expected on the site is lacking due to cutting).

**6. Human Alteration of Polygon Vegetation Community Composition.** Score: \_\_\_\_ / 6

- 6 = Less than 5% of polygon vegetation community composition is altered by human activity.
- 4 = 5% to 15% of polygon vegetation community composition is altered by human activity.
- 2 = 15% to 35% of polygon vegetation community composition is altered by human activity.
- 0 = 35% or more of polygon vegetation community composition is altered by human activity.

**7a. Percent of Polygon Physical Site Altered by Human Activity.** Score: \_\_\_\_ / 12

- 12 = Less than 5% of the polygon is physically altered by human activity.
- 8 = 5% to 15% of the polygon is physically altered by human activity.
- 4 = 15% to 35% of the polygon is physically altered by human activity.
- 0 = More than 35% of the polygon is physically altered by human activity.

**7b. Severity of Human-Caused Alteration of Polygon Physical Site (Regardless of Percent Area).** Score: \_\_\_\_ / 3

- 3 = *No physical alterations* to the site by human activity.
- 2 = Human alterations to the physical site are *slight* in effect.
- 1 = Human alterations to the physical site are *moderate* in effect.
- 0 = Human alterations to the physical site are *severe* in effect.

**8. Human-Caused Bare Ground.** Score: \_\_\_\_ / 6

- 6 = Less than 1% of the polygon is human-caused bare ground.
- 4 = 1% to 5% of the polygon is human-caused bare ground.
- 2 = 5% to 15% of the polygon is human-caused bare ground.
- 0 = 15% or more of the polygon is human-caused bare ground.

**9. Degree of Artificial Withdrawal or Raising of Water Level.** Score: \_\_\_\_ / 9

- 9 = The water body, or wetland, is *not subjected* to artificial water level change.
- 6 = The degree of artificial water level change is *minor*.
- 3 = The degree of artificial water level change is *moderate*.
- 0 = The degree of artificial water level change is *extreme*.

**10. Comments and Observations.**

---



---



---



---

**Overall Polygon Health Rating Calculation.** The sum of scores assessed for all items is calculated as the Total Actual Score, and the sum of all possible item scores is calculated as the Total Possible Score. These Totals are entered into the Health Rating Formula shown to derive a percentage Health Rating for the polygon. The percentage Rating is then categorized into a Health Category as defined below.

**Health Rating Formula:** Health Rating = (Total Actual Score) / (Total Possible Score) X 100%

**Health Category:**

80 to 100%	= Proper Functioning Condition (Healthy)
60 to less than 80%	= Functional At Risk (Healthy, but with Problems)
Less than 60%	= Nonfunctional (Unhealthy)

**ADDITIONAL MANAGEMENT CONCERNS**

**11. Polygon Trend.** Select one: Improving, Degrading, Static, or Status Unknown Trend: \_\_\_\_\_

**12. Overflow Structure Stability.** Score: \_\_\_\_ / 6

*(If the water body is not human constructed nor structurally altered, and lacks an overflow structure, replace both Actual and Possible Scores with NA.)*

- 6 = The overflow structure is made of concrete, pipe, or armoured rock and appears stable.
- 4 = The overflow structure is unprotected or is made of other material, but still appears stable.
- 2 = The overflow structure is made of concrete, pipe, or armoured rock, but appears unstable.
- 0 = The overflow structure is unprotected or is made of other material and appears unstable.

**13. Shoreline Rock Volume and Size.**

**13a. Shoreline Rock Volume.** Rate the shoreline rock volume as the highest appropriate category:

**Score:** \_\_\_\_\_ / 3

- 3 = More than 40% of shoreline volume is rocks at least 6.4 cm (2.5 in).
- 2 = 20% to 40% of shoreline volume is rock at least 6.4 cm (2.5 in).
- 1 = 10% to 20% of shoreline volume is rock at least 6.4 cm (2.5 in).
- 0 = Less than 10% of shoreline volume is rocks at least 6.4 cm (2.5 in).

**13b. Shoreline Bank Rock Size.** Rate the shoreline rock size for the polygon as the highest category:

**Score:** \_\_\_\_\_ / 3

- 3 = At least 50% of rocks present are boulders and large cobbles (>13 cm [5 in]).
- 2 = 50% of rocks present are small cobbles and larger (>6.4 cm [2.5 in]).
- 1 = At least 50% of rocks present are coarse gravels and larger (>1.5 cm [0.6 in]).
- 0 = Less than 50% of rocks present are coarse gravels and larger (>1.5 cm [0.6 in]).

**14. Vegetative Use by Animals.** Use the categories below to score the amount of utilization.

**Score:** \_\_\_\_\_ / 3

- 3 = 0% to 25% available forage taken.
- 2 = 26% to 50% available forage taken.
- 1 = 51% to 75% available forage taken.
- 0 = 76% to 100% available forage taken.

**15. Susceptibility of Parent Material to Erosion.**

**Score:** \_\_\_\_\_ / 3

- 3 = Not susceptible to erosion (well armoured).
- 2 = Slightly susceptible to erosion (moderately armoured).
- 1 = Moderately susceptible to erosion.
- 0 = Extremely susceptible to erosion.

**16. Percent of Shoreline Accessible to Livestock.**

**Percent:** \_\_\_\_\_

**17. Percent of Tree and Shrub Cover in the Polygon that is Dead and/or Decadent.**

**Percent:** \_\_\_\_\_

**18. Break Down the Polygon Area into the Land Uses Listed (must total to approx. 100%):**

- No land use apparent: \_\_\_\_\_
- Turf grass (lawn): \_\_\_\_\_
- Tame pasture (grazing): \_\_\_\_\_
- Native pasture (grazing): \_\_\_\_\_
- Recreation (ATV paths, campsites, etc.): \_\_\_\_\_
- Development (buildings, corrals, paved lots, etc.): \_\_\_\_\_
- Tilled cropping: \_\_\_\_\_
- Perennial forage (e.g., alfalfa hayland): \_\_\_\_\_
- Roads: \_\_\_\_\_
- Logging: \_\_\_\_\_
- Mining: \_\_\_\_\_
- Railroads: \_\_\_\_\_
- Other: \_\_\_\_\_

Description of Other Usage Noted: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**19. Break Down the Area Adjacent to the Polygon Into the Land Uses Listed (must total to approx. 100%):**

- No land use apparent: \_\_\_\_\_
- Turf grass (lawn): \_\_\_\_\_
- Tame pasture (grazing): \_\_\_\_\_
- Native pasture (grazing): \_\_\_\_\_
- Recreation (ATV paths, campsites, etc.): \_\_\_\_\_
- Development (buildings, corrals, paved lots, etc.): \_\_\_\_\_
- Tilled cropping: \_\_\_\_\_
- Perennial forage (e.g., alfalfa hayland): \_\_\_\_\_
- Roads: \_\_\_\_\_
- Logging: \_\_\_\_\_
- Mining: \_\_\_\_\_
- Railroads: \_\_\_\_\_
- Other: \_\_\_\_\_

Description of Other Usage Noted: \_\_\_\_\_  
\_\_\_\_\_